Date:

Thursday, 19/06/2008 9:53:42 AM

User:

Customer Job Number Julie Lecocq

: CU-DAR001 Dart Helicopters Services

S.O. No. :

: 39951 : 13034

Estimate Number P.O. Number

**Previous Run** 

This Issue : 19/06/2008

: NC Prsht Rev.

: 11 First Issue

: 37060

: SMALL /MED FAB Type

DD verified by: EC

**Drawing Revision** Material

**Process Sheet** 

**Drawing Name** 

Part Number

**Drawing Number** 

Project Number

**Due Date** 

: 30/06/2008

: D36509

: N/A

: B

. D3650 REV.B

: TOP PANEL ASS'Y

Qty:

2 Um:

Each

Written By Checked & Approved By

Comment

07-09-27 New Issue Est Rev:B ECN 1113P 08-01-22

Est Rev:C ecn1162

DD verified by: EC

08-04-02 DD verified by: EC

**Additional Product** 

Job Number:



Seq. #:

Machine Or Operation:

Description:

1.0

M304S26GA

304/316 0.018 SHEET



Comment: Qty.:

0.0536 sf(s)/Unit Total:

0.1071 sf(s)

304/316 SS sheet 26 ga (0.018" thick)

Batch: 108 415

2.0

WATER JET





**Comment: FLOW WATER JET** 

1-Cut as per Dwg D3650

Dwg Rev:

B 8-6-26

Prog Rev:



2-Deburr if necessary

3.0

QC2

PB 9-6-26



Comment: INSPECT PARTS AS THEY COME OFF MACHINE

4.0

5.0

SECOND CHECK

Comment: SECOND CHECK **BRAKE NC** 





Comment: NC BRAKE

Form as per Dwg D3650



## **Dart Aerospace Ltd**

STEP	PROCEDURE CHANGE	В	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector	
		·					
	STEP	PROCEDURE CHANGE	PROCEDURE CHANGE By	PROCEDURE CHANGE By Date	PROCEDURE CHANGE By Date Qty	PROCEDURE CHANGE BY Date Qty Chief Eng /	

Part No: _	PAR #:	Fault Category:	NCR: Yes No	DQA:	Date:
			QA: N/C C	losed:	Date:

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
		Description of NC		Corrective Action Section B				A
DATE	STEP	Section A	Initial Chief Eng	Action Description Chief Eng	Sign & Date	Verification Section C	Approval Chief Eng	Approval QC Inspector
· · · · · · · · · · · · · · · · · · ·								

NOTE: Date & initial all entries

Date:

Thursday, 19/06/2008 9:53:42 AM

User:

Julie Lecocq

**Process Sheet** 

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: TOP PANEL ASS'Y

Job Number: 39951

Part Number: D36509

Job Number:



Seq. #:

**Machine Or Operation:** 

Description:

6.0 QC5

INSPECT WORK TO CURRENT STEP



Comment: INSPECT WORK TO CURRENT STEP

7.0

8.0

PACKAGING 1

PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

Identify and stock Location:

QC21

FINAL INSPECTION/W/O RELEASE



08/07/17/

Comment: FINAL INSPECTION/W/O RELEASE

Job Completion



MF 08-07-16

Dart Ae	rospace L	td								
W/O:			WC	ORK ORDER CHANGI	ES					
DATE STEP		PROCEDURE CHANGE				Ву	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector
Part No	:	PAR #:	Fault Cate	gory:	_ NCR	: Yes I	No <b>DQ</b>	A:	_ Date: _	<del></del>
						QA: N/	C Close	d:	_ Date: _	
NCR:			WORK ORDI	ER NON-CONFORMA	NCE	(NCR				
DATE	STEP	Description of NC	<del></del>	Corrective Action Section	on B		Verific	cation	Approval	Approval
DATE	SIEF	Section A	Initial Chief Eng	Action Description Chief Eng		Sign & Date	Secti		Chief Eng	QC Inspector
								:		
* .*										

NOTE: Date & initial all entries

DART AEROSPACE LTD	Work Order: 3995
Description: Angle	Part Number: D3650-9
Inspection Dwg: D3650 Rev: B	Page 1 of 1


## FIRST ARTICLE INSPECTION CHECKLIST

	Х	First Article	Prototype
--	---	---------------	-----------

		,	,				
Drawing Dimension	Tolerance	Actual Dimension	Accept	Reject	Method of Inspection	Com	ments
Ø0.098	+0.004/-0.001	,100	M		V		
0.89	+/-0.030	, 861	*		V		
1.07	+/-0.030	1.077	×		V		
0.28	+/-0.030	. 38	*	-	V		
6.05	+/-0.030	86,	X		$\mathcal{J}$		
0.55	+/-0.030	,55	*		V		
8.19	+/-0.030	28, 18	×		<b>√</b>		
							·
			<u> </u>				
· · · · · · · · · · · · · · · · · · ·							
	-						
	-						
				·			
······································							
<del></del>							-
	-						
		<del>,</del>					<del></del>
							,
·		_					
						,	
							_
easured by:	<u>\$</u>	Audited by:	>,	1	Prototype Ap	proval:	N/A
	9-6-26	Date:	0/8/0	4/2/		Date:	N/A

Measured by: \\&	Audited by:	201	Prototype Approval:	N/A
Date: 9-6-36	Date:	06 au 06	Date:	N/A

Rev	Date	Change	Revised þy	Approved
Α	08.04.17	New Issue	KJ/DD 🛠	



7) WEIGHT: 3.3 lbs

AN3C-3A BOLT (1) AN960C10 WASHER (1) (8 PLACES) D3650-5 FWD PANEL (REF) -D3650-3 CENTER PANEL (REF) -D3650-1 AFT PANEL (REF)

2

PA	RT	LI	ST
----	----	----	----

QTY -041	PART NUMBER	DESCRIPTION
X	D3650-041	TUNNEL TOP PANEL ASSEMBLY
1	D3650-1	AFT PANEL
1	D3650-3	CENTER PANEL
1	D3650-5	FWD PANEL
8	AN3C-3A	BOLT
8	AN960C10	WASHER

RETURN TO SHEETS 1, 2 & 7: UPDATED FASTENER QUANTITIES; UPDATED VIEWS
SHEETS 3 & 8: REMOVED/RELOCATED HOLES; UPDATED VIEWS
SHEET 4: 1.8 WAS 1.5; 1.0 WAS 0.8; UPDATED VIEW; ADDED NOTE 8
SHEET 5: REMOVED NOTE IN C6 & ASSOCIATED DIMS; UPDATED VIEWS
SHEET 6: REMOVED/RELOCATED HOLES & ADDED CUTOUT TO D3650-3F; MOVED D3650-11/-11F TO SHEET 9; ADDED DETAIL I SHEET 9: RELOCATED D3650-11/-11F FROM SHEET 6; UPDATED DIMS OF D3650-11/-11F INGINEERING UNCONTROLLED COPY SUBJECT TO AMENDMENT 08.01.07 WITHOUT NOTICE

SHOP COPY

**NEW ISSUE** Α 07.11.07 REV. DESCRIPTION BY DATE DESIGN RF DART AEROSPACE LTD DRAWN HAWKESBURY, ONTARIO, CANADA DRAWING NO. CHECKED REV. B D3650 MFG. APPR. SHEET 1 OF 9  $\cap$ APPROVED TITLE SCALE TOP PANEL ASSEMBLY DE APPR.

COPYRIGHT © 2007 BY DART AEROSPACE LTD


IT IS PRIVATE AND COMPRIENTIAL AND IS SUPPLED ON THE EXPRESS CONDITION THAT IT IS


EED FOR ANY PURPOSE OR COPED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT


DATE


08.01.07


8














2 3 8 D D - 0.11 (TYP) 11.69 -R0.13 (TYP) Ø0.21 1.14 -(8 PLACES) UP 30° R0.06 (REF) 1.93 Ø0.098 (40 DRILL) (DIMPLE HOLES FOR MS20427M3 B DOWN 30 ° RO. 06 (REF) B 0.344 RIVET (TYP) (TYP) 5.87 8.34 8.23 -G 9.18 Ø0.213 (TYP) 10.45 - 0.35 (TYP) DOWN 28 ° RO.06 (REF) DOWN 62 ° R0.06 (REF) **DETAIL G** UP 90 ° R0.06 (REF) 1.17 Ø0.098 (40 DRILL) - 0.351 (DIMPLE HOLES 10.11 0.40 (TYP) Ø0.213 (TYP) FOR MS20427M3 (3.370 PITCH BOTH SIDES) В RIVET (TYP) 0.78 (TYP) 11.71 **SHOP COPY** RETURN TO ENGINEERING UNCONTROLLED COPY - 0.312 SUBJECT TO AMENDMENT D3650-5F FLAT PATTERN DETAIL H WITHOUT NOTICE WORK ORDER (2 PLS) NOTES: 1) MATERIAL: AISI 304/316 STAINLESS STEEL 0.018 THICK (26 GAUGE) SHEET, PER MIL-S-5019 (REF. DART SPEC. M304S26GA) DESIGN RF DART AEROSPACE LTD 2) FINISH: NONE
3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
4) UNITS: INCHES UNLESS OTHERWISE NOTED
5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
6) IDENTIFICATION: NONE
7) WEIGHT: 0.6 lb DRAWN RF HAWKESBURY, ONTARIO, CANADA DRAWING NO. CHECKED W REV. B D3650 MFG. APPR. SHEET 8 OF 9 TITLE **APPROVED** SCALE TOP PANEL ASSEMBLY

COPYRIGHT® 2007 BY DART AEROSPACE LTD

THIS DOCUMENT IS PRINATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDIT

NOT TO BE USED FOR ANY PURPOSE OR COPPED OR COMMUNICATED TO ANY OTHER PERSO. DE APPR. 1:3 DATE 08.01.07

8

5

